



定格総荷重表 200t吊クローラークレーン(KH1000L)特殊									単位:t
ブーム長さm 作業半径m	33.0m	36.0m	39.0m	42.0m	45.0m	48.0m	51.0m	54.0m	
9.0	112.2								
10.0	94.6	94.4	92.8						
12.0	71.8	71.5	71.3	71.1	71.0	69.9			
14.0	57.4	57.1	57.0	56.7	56.6	56.5	56.2	56.0	
16.0	47.5	47.2	47.1	46.8	46.7	46.6	46.3	46.0	
18.0	40.4	40.1	39.9	39.7	39.5	39.4	39.1	38.8	
20.0	35.0	34.6	34.4	34.2	34.0	33.9	33.6	33.3	
22.0	30.7	30.4	30.2	29.9	29.7	29.6	29.3	29.0	
24.0	27.3	26.9	26.7	26.5	26.3	26.2	25.8	25.5	
26.0	24.5	24.1	23.9	23.6	23.5	23.3	23.0	22.7	
28.0	22.2	21.8	21.6	21.3	21.1	20.9	20.6	20.3	
30.0	20.3	19.8	19.6	19.3	19.1	18.9	18.6	18.3	
32.0		18.2	17.9	17.6	17.4	17.2	16.8	16.6	
36.0				14.8	14.6	14.4	14.0	13.7	
40.0					12.5	12.2	11.9	11.6	
44.0							10.2	9.8	
48.0								8.5	
フックブロック質量(ton)									
フックの種類	200t用	100t用	60t用	25t用	12.5t用				
質量	2.6	1.4	1.2	0.85	0.5				

第21吉野号	尺度 1:500
KH-1000L定格総荷重表	H24.07.01
吉野建設株式会社	